New path lighting to be installed.

New ladder access to basement. Exact details to be confirmed.

Existing cupboard overhauled and adapted as Flower arranging area.

Lauden storage chest to remain.

New storage cupboards for equipment and/or chairs with a design to match that of neighbouring cupboards. See Detail.

New Notice Boards with storage under for kneelers and sloped display for leaflets and information. Design to be agreed by others.

Ensure that medieval paintings are adequately protected during the works.

New door with timber frame and glazed infill with applied manifestation. See Detail.

Entrance mat - details tbc.

Existing historic timber oak door retained

Timber panelling along length of wall removed and wall made good where required. Wall area to be assessed following removal for any remnants of historic wall paintings that may be covered.

WWI memorial to centre of wall to be repositioned to accommodate inclusion of WWII assembly from South side of church. Exact layout to be agreed.

New threshold stone to ensure seal to underside of new door.

Open passage under cupboards.

ORGAN

Additional step up to Organ.

NORTH EXTENSION

Existing Radiators to remain but altered to heating engineers details

New cupboard constructed to accommodate churn kit with storage over. See Detail.

Existing pews removed including choir stalls in front of the screen.

VESTRY

99.720

Curtain rail above door to be removed.

Pulpit adjusted to suit new steps and altered so that it can be moved as one unit if desired.

Sanctuary dais to be removed and leveled with chancel floor.

Holes to pilasters to be filled and made good including redecoration.

Assumed possible chalk tombs - tbc.

Font

Font to be relocated to position indicated. A new stone base to match the existing to size shown is to be installed under.

Recorded, known tomb positions underfloor.

Existing step in floor and raised area removed.

New carpet finish throughout Chancel and North & South Extensions.

New communion table to be confirmed. Design by others.

99.755

Timber Pew platforms removed and floor reinstated with lime concrete slab and finished with a honed limestone random pattern.

TOWER

NAVE

CHANCEL

New step formed to meet new level of floor and that of existing chancel floor.

Reredos made good following lowering of floor and localised areas of repair.

New removable altar rails to be positioned as required. Design by others.

Holes to pilasters to be filled and made good including redecoration.

1500

Handrail added to Chancel Pillar.

Wheelchair turning circle.

Display space

New disabled ramp linking Nave and chancel levels. See Detail.

Wheelchair turning circle.

1500

Existing Radiators to remain but altered to heating engineers details

Existing timber partitions removed and disposed of enclosing quiet area.

WWII memorial relocated due to creation of new South door.

SOUTH AISLE

New threshold stone to ensure seal to underside of new door.

SOUTH TRANSEPT

SOUTH EXTENSION

New step formed to meet new level of floor and that of existing chancel floor finished neatly against ramp.

100.000

Existing step in floor and raised area removed.

New Storage cupboard seating over and lift up lids. See Detail.

New door opening formed through retained surround and walls made good locally.

New porch to existing south door surround. See Detail.

New door with timber frame and glazed infill with applied manifestation as North.

New gullies with connecting pipe under.

New threshold chain to front porch.

Gravestone removed

Ground re-graded locally to suit level from porch.

99.755

Level threshold and door adjusted to suit altered depth. Allow for making good to stone threshold and frame following adjustment of floor.

Existing door handed with retasted frame and brush and seals.

Existing Electrical intake unit to remain.

VESTRY

Carpet removed and wood block floor exposed. Allow for isolated repair following removal.

SOUTH DOOR

New landscaped path to South Door. Materials to match existing.

Loft Hatch

Walls to be made good where required and decorated.

Tea / coffee point with new kitchen worktop and units above and below

Cleaners Cupboard with Sink

Cpd

Cpd

Cleaners Cupboard

New additional wc

WC

WC

New disabled wc with baby changing facilities

Vinyl floor finish to WC's

0 5

SCALE 1:50 (A1)
SCALE 1:100 (A3)

METRES

DO NOT SCALE DRAWINGS THE CONTRACTOR IS RESPONSIBLE FOR CHECKING DIMENSIONS & ANY DISCREPANCY IS TO BE REFERRED TO THE ARCHITECT.

N O T E S

All commemorative plaques from within the church to be removed and assembled on dedicated memorial board. Exact position to be confirmed together with design of board

Any commemorative plaques affixed to pews shall be removed and stored before the pews are dismantled.

Floor tiles shall be removed and set aside (to include the area under the gallery in the north-west corner of the church).

Woodblock in the south aisle shall be removed.

Wooden chairs shall be cleaned and stored for potential future use.

The font shall be temporarily removed and safely stored on-site.

The Holy table and communion rails shall be removed and stored for possible future use.

The short sections of timber skirting at the base of the pilasters behind the Holy Table shall be removed and kept for reinstallation.

Fixed timber pews in the north extension shall be removed and dismantled to allow for possible alter reinstatement or other reuses.

REV.	AMENDMENT	DATE
P1	For Comment	18.02.11

THOMAS FORD & PARTNERS
CHARTERED ARCHITECTS SURVEYORS
177 KIRKDALE
SYDENHAM • LONDON • SE26 4QH
TEL 020 8659 3250 • FAX 020 8659 3146
EMAIL tfp@thomasford.co.uk

PROJECT
FARNBOROUGH
ST. PETERS CHURCH
RE-ORDERING PROJECT

TITLE
FLOOR PLAN
AS PROPOSED

DRAWN	DATE	SCALE	CHECKED
MJN	JAN 2011	1:50 @ A1	
PROJECT REF.		DWG. No.	REV.
667102		GA - 101	P1